



**Palmex Hawaii
&
Aloha Tiki Huts**
P.O. Box 3626
Kailua Kona, HI, 96745
(808) 854-1312



PROPOSAL

TURN KEY TIKI HUTS

THANKS FOR YOUR INTEREST IN PALMEX SYNTHETIC THATCH AND ALOHA TIKI HUTS .

TURN KEY OHIA FRAME HUTS INCLUDE :

- . 6"-7" DIAM POSTS , 4"-5" DIAM BEAMS , 2"-3" DIAM RAFTERS AND BRACING,
- . SANDED AND DETAILED OHIA POSTS , BEAMS ,RAFTERS AND BRACING .
- . TWO STEP SIKKENS (NATURAL SHADE) TREATMENT.
- . 3/8" DIAM MANILLA ROPE LASHING WITH VARATHANE TREATMENT .
- . PALMEX BRAND SYNTHETIC THATCH , BORABORA OR ALOHA MODEL LEAVES
- FIRE RETARDANT LEAVES AVAILABLE ON REQUEST
- . OFF SITE CONSTRUCTION AND ON SITE RE ASSEMBLE CONSTRUCTION

TURN KEY HUTS ARE PRICED AS :

- . SINGLE PITCH SHED ROOF @ \$75.00 PER SQ FT OF COVERED AREA
- . GABLE ROOF @ \$80.00 PER SQ FT OF COVERED AREA
- . HIP ROOF @ \$90.00
- . ROUND ROOF @ \$95.00

EXAMPLE: POSTS SET AT 8' X 8' WITH A 18" OVERHANG GIVES A COVERED AREA OF
11' X 11' = 121 SQ FT

EXCAVATION OR CONCRETE NOT INCLUDED

SHIPPING AND OFF ISLAND ACCOMMODATIONS NOT INCLUDED